

Departure - Outside

- Dump tanks
- Store all ground items
 - Chairs
 - Mat
 - Grill
 - Rear Stabilizer Jack
- Retract awnings
- Clean slide tops
- Close microwave vent
- Remove and store all noodles - then use EXTRA CAUTION
 - Slides
 - Pin box
- Disconnect/store attachments - **check with inside before disconnecting**
 - Water
 - Sewer
 - Cable
- *** Wait until clearance from inside and slides are retracted ***
- Retract slides
- Hitch truck
 - Lower tailgate,
 - Raise pin box
 - Back truck under trailer
 - Lock hitch
 - Safety cable
- Retract landing gear
- Electric
 - Unhook electric cord and stow
 - Plug in truck
 - Raise tailgate
- Pull/store landing gear blocks
- Store steps and handle
- Check brakes/lights
- Final walk-around
- Turn on TPMS
- Test trailer brakes on departure

Departure - Inside

- Lower TV antenna
- Store satellite antenna
- Close windows
- Store bedroom
 - Clear floor area for slide
 - Close and latch closet
 - Unsecured items on bed
- Store bathroom
 - Roof vent closed
 - Shower items on floor
 - Shower door latched
 - Sliding door latched
- Store living room/kitchen
 - Turn off ceiling fan
 - Ensure slide clearance with living room furniture
 - Noodles on refrigerator and in between door handles
 - Sink lids in place
 - Roof vent closed
- Rugs stored
- Sweep/vacuum floor
- Trash out
- Lights off
- Air conditioners off
- Retract slides - **Check with outside before retracting**
- Steps and handle stored

Arrival Set Up

- Ensure slide clearance at site
- Place blocks under front landing gear (if necessary)
- Extend front landing gear
- Unhook truck
 - Lower tailgate
 - Safety cable
 - Latch
 - Unplug truck
 - Pull forward
- Autolevel trailer
- Test and hook up shore power
- Hook up water/sewer
- Inside - ensure slides are clear from any shifting
- Extend slides
- Install noodles
- Raise satellite antenna
- Extend awnings
- Set up outside gear